

PROPOSAL

7TS 29-31 Snowflake

PREPARED BY

Siemens Industry, Inc. ("Siemens")

PREPARED FOR

NORTHERN WOLVES INC

DELIVERED ON

June 02, 2026

SMART INFRASTRUCTURE

Transforming the Everyday



Table of Contents

SIEMENS PROPOSAL 3

 Contact Information 3

 Scope of Work 4

 Inclusions 7

 Exclusions 8

 Clarifications 9

 Sell Price..... 10

 Payment Terms..... 11

TERMS OF SALE 12

 Siemens Terms of Sale (STS) 12

Signature Page 13

 Signature Page 13

Contact Information

Proposal #:	10559656
Date:	June 02, 2026

Sales Executive:	Brian Greda
Branch Address:	412 Mount Kemble Ave Morristown, 07960
Telephone:	973.332.0789
Email Address:	brian.greda@siemens.com

Customer Contact:	
Customer:	NORTHERN WOLVES INC
Address:	55 9TH ST
	BROOKLYN NY 11215-6843
Services shall be provided at:	BOSTON PROPERTIES
	7 TIMES SQUARE C 2 LEVEL NEW YORK NY 10036

9dd43b11-0b48-4494-85b0-e16962a46f7c

Scope of Work

Siemens proposes the following:

Furnish and install the Siemens Building Management System (BMS) in accordance with the drawings and specifications by AMA Consulting Engineers.

- Mechanical plans dated 4/03/2026 - Issued for pricing
- Specification on plans
- Mechanical plans dated 4/22/2026 - Addendum #1

Detailed Scope of Work

The following list of equipment will be controlled and/or monitored by the BAS:

Qty	System Description
3	PXC BMS Primary Controllers
93	Fan Powered Boxes
3	Water Cooled AC units
6	CW Pumps
5	Fire Smoke Dampers
11	Pantry Sink / closet Leak Detectors
6	HW Heater Leak Detectors
3	Tenant Auto Dialers
	Alternate pricing - See below

The following equipment/systems will be controlled and/or monitored by the Siemens BMS as described. For counts per area refer to the above list of equipment per the breakdown:

General (building standards)

- - Use of plenum rated cabling for low voltage in open ceilings
 - Orange FLN / Comm Wire
 - Thermostat – Sensing only
 - 2/3 Static pressure resides in AC unit - run out Double gang poly and tip
 - Only tenant leak alarms to BMS. All other tenant equipment alarms to tenant Autodialer.
 - Leak Detector Liebert LT-410 only (building standard)
 - Laptop for ABT project on site. Use Laptop for all DXR projects. Contact Siemens CSM.
 - Field coordinate with Fire alarm contractor to provide new Fan Powered Box Shut Down contact at Mammoth AC unit DDC panel.

- OPEN SHOP Electrical Subcontractor

PXC DDC Controller

- Siemens to replace / upgrade existing primary DDC controller to enable communication to new FPB controllers via BACnet MSTP.
 - Re- connect existing BLN to new controller
 - Install new Ethernet cable to adjacent Base Building IT closet and safe-off for future connection (BB IT contractor to install future network switch).
 - Fire Alarm contractor to provide new shut down / status relays within 3ft of controllers
 - Re-install new differential pressure transmitter for existing AHU (removed during demo).

Water Cooled AC Units

- Water cooled AC units to be provided with manufacturer controls. Siemens to provide wiring and devices as follows:
 - Interlock wiring between CRAC and WCCU
 - Install and wire manufacturer's temperature/humidity room sensor
 - Hardwire interlock unit operation to pumps
 - Furnish (2) Isolation valves
 - Furnish and wire (2) Leak detectors (1-Condensing Unit / 1-to alarm at Base Building BMS and Tenant Autodialer. Leak detectors to close isolation valves upon alarm.

FP Boxes w/ Hot Water Reheat

- Siemens to provide factory mounted controls on FP boxes, and field FLN communication wiring. The following is a list of the factory mounted controls, monitored and controlled by Siemens:
 - (1) DXR BACnet MSTP equipment controller with damper actuator
 - (1) Fan - Start/stop and status
 - Current sensor p/n: ECMCS (Automation Components)
 - (1) Room Temperature Sensor – Sensing Only
 - (1) Discharge Air Temperature Sensor
 - (1) Hot Water Valve and Actuator
 - **Add Freeze protection program per Building standard.**
 - **Add Unoccupied mode program: Dampers full-open to prevent Mammoth unit shut down.**

CW Pumps

- Siemens to wire pumps and associated sensors to local lead / lag panel (provided by others).
 - (1) Install and power manufacturer provided Lead / Lag panel
 - (2) Isolation valves - furnish and wire
 - (2) Leak detectors - furnish and wire. To alarm at BB BMS and Tenant AutoDialer
 - (2) Flow Switches - furnish and wire
 - (2) Pump - Start/stop and Status
 - (1) Differential pressure transmitter - to maintain pump speed
 - (1) Hardwire interlock to AC unit operation

- No connection to base building BMS
- Lead Lag panel provided by others

Fire Smoke Dampers

- Siemens to furnish pneumatic labor to connect pneumatic tubing to new FSDs and existing Fire Alarm contacts. FSD dampers to operate in conjunction with existing FSDs serving Mammoth Unit

Leak Detectors - Pantry Sink and HW Heaters

- Siemens to furnish and install Leak detectors. Hardwire interlock to isolation valve (valve furnished, installed, and powered by others).
 - Leak detectors to alarm at BB BMS and Tenant AutoDialer

Autodialer

- Siemens to furnish and install tenant autodialer. Tenant to provide IP connection.

Alternate Price

1. ~~Add \$125 per Fan Powered Box~~ - (1) Field install controller in lieu of factory mounting.
2. ~~Add \$575 per CO2 room Sensor~~ - if required. Specification calls for CO2 monitoring in large areas, but plans do not show CO2 room sensors.... only show room temperature sensors.
3. ~~Add \$2,800 per Panel~~ - Furnish (1) pump Lead / Lag DDC panel with software. Stand-alone. No tie-in to BMS
4. ~~Add \$62,200~~ - Conduit stub-ups and backboxes for thermostat installation (if required)
5. ~~Deduct \$84,300~~ - Open shop labor for electrical labor **ACCEPTED and INCLUDED**

Inclusions

1. Labor to provide Siemens standard submittals / record documents
 - System architecture (Siemens BACnet IP & MSTP)
 - Network address schedule
 - System flow diagrams
 - Control installation / wiring diagrams
 - Control & Component Panel layouts
 - Valve schedule
 - Equipment / Instrumentation datasheets
 - Point database
2. Labor to provide installation and wiring, to include:
 - BMS conduit as specified
 - BMS control and interlock wiring
 - **OPEN SHOP Electrical Subcontractor**
3. Labor to provide Siemens standard startup & checkout
 - Point database verification
 - Point-to-point
 - Loop checks
 - Sequence verification
4. Labor to provide Siemens project management, to include the following:
 - BMS project scope only and associated meetings and coordination as required by project schedule (not full-time project manager)
 - Project meeting attendance
 - Project documentation requirements
 - Coordination with trades
 - Subcontractor management
 - Material ordering and delivery coordination
 - Project turnover documentation support
5. Labor to provide 12 **hours** of test and balance (TAB) support
6. Labor to provide 16 **hours** to support Commissioning Agent, to include
 - Commissioning of BMS
 - Commissioning / Validation of BMS
7. Labor to provide **2 hours** of Owner training
8. **1-year** parts and labor warranty upon beneficial use of systems

Exclusions

1. Conduit stub-ups and backboxes for thermostats
2. Conduit in open ceilings for low voltage & communication wiring (cable/wire to be plenum rated)
3. Instantaneous hot water heaters (i.e. serving eye wash stations)
4. PRV Stations, water meters, electric meters.
5. Furnishing Lead / lag panels for pumps
6. Base building BMS monitoring/control of (except Leak Detection):
 1. Pumps
 2. Water Cooled Computer room AC units
 3. Transfer Fan
 4. **Exhaust fan Dish Room**
7. Field installation of Fan Powered Box controls
8. Furnishing plumbing Isolation valves (i.e. HW heaters, sinks, etc..)
9. Air Purification System
10. CO2 sensors (none shown on plans)
11. Overtime
12. Per project aggregate general liability insurance
13. 120VAC Power wiring to all terminal box controllers
14. Furnishing, installing, or wiring of duct smoke detectors
15. Wiring for fire alarm shutdown of Fan Powered Box and/or CW AC equipment
16. Furnishing CW AC thermostats
17. FPB box control transformers
18. Installation of pipe mounted devices (i.e. control valves, flow meters, sensor wells)
19. Access doors
20. Temporary or standby labor and services

Clarifications

1. Cost for Phasing and/or Escalation has not been included. Project completion estimated within twelve (12) calendar months from reception of Purchase order / contract.
2. Price based on a **Capital Improvement** project. Appropriate taxes will be added to final sale price if certificate is not provided.
3. Sample Certificate of Insurance must be provided with contract / purchase order. Required Insurance must be listed in commitment document.
4. **Estimated durations** are as follows from acceptance of PO / Contract:
 1. Purchase order / contract processing to activate Job number (internal) - 6 to 8 business days
 2. Submittal - 1st submission - 2 to 4 weeks from job activation
 3. On site installation to begin - upon approval of submittals
 4. Material shipments are experiencing unusually long lead times
5. The project cost includes the tie in of the associated BMS system to the existing Siemens BMS front end workstation
6. Graphic floorplan can only be generated from the Autocad files provided. Please provide the correct floorplan area(s) (full/partial) required to be displayed on the BMS.
7. Control wiring shall be run in conduit where exposed to outdoor conditions. Control wiring shall be run using plenum rated cable without conduit in all other locations
8. Miscellaneous wiring or power to 3rd party equipment has not been included, unless noted in Scope of Work section of this proposal.
9. If Per project Aggregate insurance is required: Add 1.1% to final sale (Per Aggregate Insurance would be noted in Cert. Of Insurance provided by GC / Building owner).

Sell Price

Total Quote Price	\$634,000.00*
-------------------	---------------

This price is firm for 30 days from the date of this proposal.

**Siemens reserves the right to adjust prices to reflect the impact of any new or modified taxes, duties, tariffs, or equivalent measures, whether direct or indirect, imposed by any U.S. or foreign governmental authority that are applicable to our offering, including any hardware, software, or service components contained therein.*

Payment Terms

Payment Terms Acceptance Agreement

The total price of: \$634,000.00 and the estimated return on investment are based on the items outlined in this proposal. ANY STATEMENTS MADE HEREIN REGARDING SAVINGS THAT MAY BE ACHIEVED BY IMPLEMENTING THE SERVICES OFFERED IN THIS PROPOSAL ARE ESTIMATES ONLY. NO WARRANTY, EITHER EXPRESSED OR IMPLIED, SHALL BE CONSTRUED TO ARISE FROM SUCH STATEMENTS, NOR SHALL SUCH STATEMENTS BE CONSTRUED AS CONSTITUTING A GUARANTEE BY SIEMENS THAT SUCH SAVINGS WILL OCCUR IF THE SERVICES ARE IMPLEMENTED.

The Buyer acknowledges that when accepted by the Buyer as proposed by Siemens Industry, Inc., this Proposal and the Siemens Buildings Projects Business Standard Terms and Conditions, (together with any other documents incorporated into the forgoing) shall constitute the entire agreement of the parties with respect to its subject matter. BY EXECUTION HEREOF, THE SIGNER CERTIFIES THAT (S)HE HAS READ ALL OF THE TERMS AND CONDITIONS AND DOCUMENTS, THAT SIEMENS OR ITS REPRESENTATIVES HAVE MADE NO AGREEMENTS OR REPRESENTATIONS EXCEPT AS SET FORTH THEREIN, AND THAT (S)HE IS DULY AUTHORIZED TO EXECUTE THE SIGNATURE PAGE ON BEHALF OF THE BUYER.

Proposal is valid for thirty (30) days from the delivery date of June 02, 2026. Payment is due within 30 days of invoice date.

Payment Terms: progress payments

Total: \$634,000.00

Siemens Industry, Inc. invoices paid by credit card may be subject to a surcharge of up to 2%.

Siemens Terms of Sale (STS)

Terms of Sale (Click to download)

[Base Terms \(United States\)](#)

Buyer agrees that Siemens shall be authorized, at its discretion and without consent, to utilize any of its world-wide affiliates to perform (subcontract) work under this Agreement. (Buyer agrees that) Buyer's data may be viewed or accessed from outside the United States by Siemens world-wide affiliates. Buyer data may be stored and/or accessed in the United States or other countries in which Siemens or our (subcontract) affiliates operate.

Price Escalation. If, during the term of this Contract, the price of various materials or labor or logistics are increased as reflected by CRU/IHS Markit/CMAI/COMEX market index, then Siemens may increase the Contract Sum or apply a surcharge to Customer accordingly.

To the extent applicable, the following Supplements are incorporated and made part of the Siemens Terms of Sale:

Click on supplement(s) below to read/download

[Solutions Supplemental Terms](#)

[Hardware Supplemental Terms](#)

The order of precedence is stated in the Base Terms (United States).

To the extent the Offerings are purchased through an existing master or frame agreement, the terms and conditions of that agreement shall apply instead of the Siemens Terms of Sale.

Siemens reserves the right to adjust prices to reflect the impact of any new or modified taxes, duties, tariffs, or equivalent measures, whether direct or indirect, imposed by any U.S. or foreign governmental authority that are applicable to the Offerings, including any hardware, software, or service components contained therein.

Siemens is entitled to amend these terms and conditions at any time without prior notice. Previous and Retired versions of Base Terms & Supplemental Terms can be found here: www.siemens.com/terms-of-sale

Signature Page

Proposed by:

Siemens Industry, Inc.

Company

Brian Greda

Name

10559656

Proposal #

\$634,000.00

Proposal Amount

June 02, 2026

Date

Accepted by:

NORTHERN WOLVES INC

Company

Name (Printed)

Signature

Title

Date

Purchase Order # ☐ PO for billing/pmnt only ☐ PO not required