P.H. Works Inc
(718)-414-1083
762 Empire Blvd #3F
Brooklyn, NY 11213

Estimate

Date	Estimate #
11/4/2026	12845

Name / Address	Ship To
Northern Wolves 55 9th Street, unit 55A-2 Brooklyn, New York, 11215	18 Vesey St Manhattan, NY 10007

Rep	Project
	18 Vesey St

Description	Qty	Rate	Total
In order to install boiler per plans # M01244603-S5: 1. Pull a BE permit with the DOB 2. Install customer supplied boiler on concrete pad (see note #1) 3. Redo near boiler piping 4. Supply and install controls to code including 1 manual reset LWCO, 1 manual reset aquastat, 1 PRV, and 1 backflow preventer 5. Reconnect wiring to boiler from existing shutoff switch 6. Supply and install emergency shut off switch outside boiler room. 7. Interlock boiler with existing motorized damper 8. Connect to existing exhaust venting 9. Call for DOB inspection 10. Obtain boiler card and signoff This price includes: 1. Permit and inspections 2. ACP5 3. All labor and materials needed to perform the above scope 4. Obtaining boiler card This price does not include: 1. Furnishing boiler and 2. Asbestos or lead removal 3. Thermostat or heating control. 4. Any gas or plumbing work 5. Any electrical work beyond the emergency shutoff switch 6. Plans or PAAs 7. Any city fees 8. Any waterproofing or flashing of penetrations 9. Chimney affidavit		23,400.00	23,400.00T

Subtotal	
Sales Tax (8.875%)	
Total	

P.H. Works Inc
(718)-414-1083
762 Empire Blvd #3F
Brooklyn, NY 11213

Estimate

Date	Estimate #
11/4/2026	12845

Name / Address	Ship To
Northern Wolves 55 9th Street, unit 55A-2 Brooklyn, New York, 11215	18 Vesey St Manhattan, NY 10007

Rep	Project
	18 Vesey St

Description	Qty	Rate	Total
10. ConEd case or gas authorization 11. Vibration pad for boiler - a price can be provided upon request Notes: 1. Customer is responsible to provide vibration pad for boiler with 1" sway, and for removing existing boiler from site. 2. Per plan, pumps and motorized damper are existing and to remain. If they are found to be defective or non-functioning, new unit(s) will be required. P.H. Works is not responsible for condition of pumps or replacement. 3. Per plan, P.H. Works will connect the boiler to plumbing connections that are existing or done by others. P.H. Works is not responsible for supplying or installing any new plumbing in the building. 4. Customer is responsible for furnishing and delivering boiler and boiler pump to job site 5. Any work in the boiler room that will be required to pass inspection--PH Works will provide a punch list for any necessary work to customer upon completion of the boiler installation. 6. Customer is responsible for providing chimney affidavit prior to P.H. Works calling for boiler inspection 7. All materials are the property of PH works until final balance has been paid. 8. In event of non-payment and legal dispute, customer is responsible for any attorney fees on behalf of P.H. Works Inc 9. Any credit card processing carries an additional 4% surcharge that will be added to the total of the invoice. Payment terms: A 50% deposit is required prior to work beginning. 45% is required			

Subtotal	
Sales Tax (8.875%)	
Total	

P.H. Works Inc
(718)-414-1083
762 Empire Blvd #3F
Brooklyn, NY 11213

Estimate

Date	Estimate #
11/4/2026	12845

Name / Address	Ship To
Northern Wolves 55 9th Street, unit 55A-2 Brooklyn, New York, 11215	18 Vesey St Manhattan, NY 10007

Rep	Project
	18 Vesey St

Description	Qty	Rate	Total
upon completion of all work on site prior to calling for boiler inspection. The remaining 5% is due upon passing boiler inspection prior to signoff. **SALES TAX WILL NOT BE CHARGED IF CUSTOMER PROVIDES A SIGNED CAPITAL IMPROVEMENT FORM PRIOR TO OR ALONG WITH PAYMENT FOR THE DEPOSIT**			

Subtotal	$23,400.00
Sales Tax (8.875%)	$2,076.75
Total	$25,476.75